

ZP Construction LLC

Pennsylvania

U.S.A

zpconstructionservicellc@gmail.com

Proposal

QT-000116

Customer

L&L Desings

2000 Washington Pike

Carnegie

Pennsylvania

U.S.A

Quote Date : 09 Oct 2026

Reference# : 658 Allegheny River Blvd,
Oakmont, PA 15139

Sales person : Elvis Pina

Subject :

658 Allegheny River Blvd, Oakmont, PA 15139

Project address:

#	Item & Description	Amount
1	Scope Description Provide all necessary labor, equipment, tools, and materials to perform selective demolition of existing building components as indicated on the architectural demolition drawings, including sheet AD-1, and as required to accommodate the proposed renovations and new addition. Work Includes 1. Interior Wall Demolition: Remove designated existing interior partitions, including drywall, framing, and associated materials where indicated on the demolition plans. 2. Ceiling Demolition: Remove existing ceiling finishes and associated components in designated renovation areas as required for new construction. 3. Flooring Removal: Remove designated existing floor finishes, adhesives, and related materials. Prepare exposed surfaces for subsequent construction. 4. Door and Frame Removal: Remove designated existing doors, frames, thresholds, anchors, and associated hardware. 5. Insulation Removal: Remove and dispose of existing insulation within wall and ceiling assemblies scheduled for demolition. 6. Casework and Fixtures: Remove designated existing casework, cabinets, brackets, anchors, and associated nonstructural components. 7. Building Connection: Perform selective removal of designated existing finishes and nonstructural components at the connection between the existing building and proposed addition. 8. Debris Removal and Disposal: Collect, load, haul, and legally dispose of demolition debris generated by the work. 9. Site Cleanup: Maintain a clean and safe work area throughout demolition operations and leave affected areas broom-clean upon completion. Exclusions * Structural demolition unless specifically identified and authorized. * Asbestos, lead, mold, or other hazardous material abatement. * Electrical, plumbing, HVAC, and fire protection disconnections or modifications. * Concrete foundation demolition or excavation. * Temporary structural shoring and engineering.	9,500.00

#	Item & Description	Amount
	* Unforeseen concealed conditions.	
	General Conditions	
	All demolition work shall be coordinated with the general contractor. Existing construction designated to remain shall be protected against damage. Any unforeseen conditions or additional demolition requirements shall be reported before proceeding.	
	Sub Total	9,500.00
	Total	\$9,500.00

Notes

Looking forward for your business.

Terms & Conditions

This quote does not include any additional repairs or labor outside of the scope of work mentioned above. Painting services are not included. Dumpster services are not included. All services outside of the scope of work will not be performed without an additional signed agreement.



Elvis Pina
Authorized Signature